



PROJECT : SUPPLY OF LABOR AND MATERIALS FOR THE REPAIR OF JARDINE-SCHINDLER ELEVATOR
LOCATION : DBP ANNEX BUILDING, MAKATI AVENUE, MAKATI CITY
SUBJECT : SCOPE OF SERVICES

The Project shall cover the supply of labor and materials for the repair of Jardine-Schindler Elevator per Scope of Services at the DBP Annex Building.

MODE OF PROCUREMENT: SMALL-VALUE PROCUREMENT

I. APPROVED BUDGET FOR THE CONTRACT (ABC): FOUR HUNDRED SEVENTY THOUSAND EIGHT HUNDRED THIRTY-NINE PESOS AND 13/100 CENTAVOS (P 470,839.13)

II. SCOPE OF WORKS

The Contractor shall hold all the obligations, duties and responsibilities necessary to the successful completion of the contract assigned to or be undertaken by the Contractor, including all labor, materials, equipment and services, other incidentals and furnishings thereof in accordance with the drawings, specifications and all addenda prepared by DBP.

- a. Delivery of materials, tools, and equipment.
- b. Dismantling of parts/materials.
- c. Supply, delivery, and installation of replacement parts per specification.
- d. Supervision of the project.
- e. General cleaning and hauling of debris.
- f. All replaced parts shall be turned over to RMU-CFMD personnel for safe keeping.

III. REQUIREMENTS/CONDITIONS

A. TECHNICAL SPECIFICATIONS

Item/Description	Quantity
Replacement kit ASIXA 32Q by ASIXA34	1 Piece
PCB GCIOA 360.Q	1 Piece
Roller Varidor 30 for hole dia 10mm	12 Piece
Guide Shoe (for sheet 1.5mm)	12 Piece
PCB FSIMM 32.Q (nowe ID => 59800170)	1 Piece
Door motor IDD32.001	1 Piece

B. OTHER REQUIREMENTS

- 1. Workers should wear their company uniform and I.D.
- 2. Defective works and materials may be rejected by DBP at any before the final acceptance of the work rebuild/replace in accordance with the specifications with the resulting expenses chargeable to his account.
- 3. The Contractor shall employ a competent supervisor acceptable to the DBP who will supervise the work on a full-time basis.
- 4. All trash, debris, including hazardous waste should be placed in trash bags, sacks, or appropriate container before disposal. DBP is an ISO 14001 certified bank and the contractor is required to observe and abide by its rules and