TECHNIAL SPECIFICATION
TRANSFORMER
SURIGAO BRANCH

I. Approved Budget for the Contract ₱175,000.00(Inclusive of VAT/applicable)

ITEM	QUANTITY
Transformer	1 - Unit

II. Technical Specification

➢ KVA	50
➢ PHASE	1
➢ CYCLE	60Hz
➢ HV BIL	95
➢ KV AC	34
➢ KV CLASS	ONAN
➢ HV	7620/13200
	6.6A
➢ LV	120/240
	208A
➢ Z%	1.9
➢ HV MATERIAL	COPPER
➢ LV MATERIAL	COPPER
➢ OIL	85L
➢ OIL	65°C
➢ COIL	65°C