



## Bid Notice Abstract

### Request for Quotation (RFQ)

**Reference Number** 12213615  
**Procuring Entity** DBP BRANCH BANKING GROUP - BICOL  
**Title** SUPPLY, DELIVERY, INSTALLATION AND TESTING & COMMISSIONING OF FIRE DETECTION ALARM SYSTEM FOR DBP LEGAZPI BRANCH, DBP DAET BRANCH, DBP IRIGA BRANCH AND DBP GUINOBATAN BRANCH  
**Area of Delivery** Albay,Camarines Norte,Camarines Sur

<b>Solicitation Number:</b>	2025-006	<b>Status</b>	<b>Pending</b>
<b>Trade Agreement:</b>	Implementing Rules and Regulations		
<b>Procurement Mode:</b>	Negotiated Procurement - Small Value Procurement (Sec. 53.9)	<b>Associated Components</b>	9
<b>Classification:</b>	Goods	<b>Bid Supplements</b>	0
<b>Category:</b>	Fire Fighting & Rescue and Safety Equipment		
<b>Approved Budget for the Contract:</b>	PHP 839,757.92	<b>Document Request List</b>	0
<b>Delivery Period:</b>	60 Day/s		
<b>Client Agency:</b>		<b>Date Published</b>	11/07/2025
<b>Contact Person:</b>	Jennifer Cordial Naval Chairperson, RBAC-Bicol Panganiban Drive Naga City Camarines Sur Philippines 4400 63-02-88189511 Ext.1596  jcnaval@dbp.ph	<b>Last Updated / Time</b>	10/07/2025 23:00 PM
		<b>Closing Date / Time</b>	23/07/2025 15:00 PM

#### Description

LOCATION : DBP LEGAZPI BRANCH  
DBP BUILDING QUEZON AVE., LEGAZPI CITY, ALBAY

DBP DAET BRANCH  
MAGALLANES IRAYA, BRGY. III, DAET CAMARINES NORTE 4600

DBP IRIGA BRANCH  
ICT BUILDING, POBLACION ROAD, STA. CRUZ SUR, IRIGA CITY

DBP GUINOBATAN BRANCH  
GF SB LEGISLATIVE BUILDING, ILAWOD, GUINOBATAN CITY, ALBAY

SUBJECT : SCOPE OF WORKS AND TECHNICAL SPECIFICATIONS

MODE OF PROCUREMENT: SMALL VALUE PROCUREMENT (INFRASTRUCTURE)

APPROVED BUDGET FOR THE CONTRACT (ABC):  
EIGHT HUNDRED THIRTY-NINE THOUSAND SEVEN HUNDRED FIFTY-SEVEN AND 92/100 (₱ 839,757.92) INCLUSIVE OF VAT/APPLICABLE TAXES

End User Approved Budget for Contract  
DAET BRANCH ₱220,856.67  
IRIGA BRANCH ₱208,878.40  
GUINOBATAN BRANCH ₱184,247.53  
LEGAZPI BRANCH ₱225,775.32  
Total Contract Price ₱839,757.92

#### SCOPE OF WORKS AND TECHNICAL SPECIFICATIONS:

The Contractor shall hold all obligations, duties and responsibilities necessary for the successful completion of the contract assigned to or be undertaken, including all labor, materials, equipment and services, other incidentals, i.e., bonds and insurance, contractor's all risk insurance (CARI); and furnishings thereof in accordance with the specifications and all addenda prepared by DBP.

#### GENERAL REQUIREMENTS

Construction health and safety program  
Clearances/permit requirements (certificate)  
Mobilization & demobilization  
Site maintenance  
Hauling/disposal

#### SITE CONDITIONS

Dismantling Works  
Dismantling of existing Fire Detection Alarm System (FDAS) device and Fire Alarm Panel, and properly turning over and securing the dismantled items in the DBP-designated storage area

#### FIRE DETECTION ALARM SYSTEM WORKS

##### IRIGA BRANCH

Installation of Fire Detection Alarm System and Accessories  
New fire Alarm control panel (addressable) with batteries  
New auto dialer (line / GSM Ready)  
New smoke detector (addressable)  
New heat detector (addressable)  
New manual call point with strobe sounder (addressable)  
Installation of wires and cables  
CAT5e UTP cable 4 pairs (305m/box)  
#16 2C AWG stranded TF wire  
Installation of conduits and fittings  
20mm dia PVC moulding (2.44m/pc)  
PVC wire gutter with cover (2000mm Lx500mm Wx50mm D)  
20mm dia flexible PVC pipe (50m/roll)  
20mm dia straight connector  
20mm dia angle connector  
Installation of boxes  
Junction box with cover (PVC)  
Utility box (PVC)  
Other accessories  
Hanger and support  
Consumables (tape, tagging, PVC cement and accessories)  
Mounting termination, testing & commissioning and programming.

##### GUINOBATAN BRANCH

Installation of Fire Detection Alarm System and Accessories  
Fire Alarm control panel (addressable)  
auto dialer (line / GSM Ready)  
Smoke detector (addressable)  
Heat detector (addressable)  
Manual call point with strobe sounder (addressable)  
Installation of wires and cables  
#16 2C AWG stranded TF wire  
CAT5e UTP cable 4 pairs (305m/box)  
Installation of conduits and fittings  
25mm dia PVC pipe (3m/pc) with adapter and locknut  
20mm dia flexible PVC pipe (50m/roll)  
20mm dia straight connector  
20mm dia angle connector  
Installation of boxes  
Junction box with cover (PVC)  
Utility box (PVC)  
Other accessories  
Hanger and support  
Consumables (tape, tagging, PVC cement and accessories)  
Mounting termination, testing & commissioning and programming.

##### LEGAZPI BRANCH

### 3.3.1 Installation of Fire Detection Alarm System and Accessories

New fire Alarm control panel (addressable) with batteries

New auto dialer (line / GSM Ready)

New smoke detector (addressable)

New heat detector (addressable)

New manual call point with strobe sounder (addressable)

Installation of wires and cables

CAT5e UTP cable 4 pairs (305m/box)

#16 2C AWG stranded TF wire

### 3.3.3 Installation of conduits and fittings

25mm dia PVC pipe (3m/pc) with adapter and locknut

20mm dia flexible PVC pipe (50m/roll)

20mm dia straight connector

20mm dia angle connector

Installation of boxes

Junction box with cover (PVC)

Utility box (PVC)

Other accessories

Hanger and support

Consumables (tape, tagging, PVC cement and accessories)

Mounting termination, testing & commissioning and programming.

### DAET BRANCH

Installation of Fire Detection Alarm System and Accessories

Fire Alarm control panel (addressable)

auto dialer (line / GSM Ready)

Smoke detector (addressable)

Heat detector (addressable)

Manual call point with strobe sounder (addressable)

Installation of wires and cables

#16 2C AWG stranded TF wire

CAT5e UTP cable 4 pairs (305m/box)

Installation of conduits and fittings

25mm dia PVC pipe (3m/pc) with adapter and locknut

20mm dia flexible PVC pipe (50m/roll)

20mm dia straight connector

20mm dia angle connector

Installation of boxes

Junction box with cover (PVC)

Utility box (PVC)

Other accessories

Hanger and support

Consumables (tape, tagging, PVC cement and accessories)

Mounting termination, testing & commissioning and programming.

### CONDITIONS OF THE CONTRACT:

The Contractor shall ensure that the items delivered are in accordance with the specifications required by DBP. DBP has the right to reject delivery if item/s delivered were found to be defective and not according to the required specifications.

The Contractor shall submit, construction schedule reflecting all activities needed to complete the project, their sequence and duration.

The Contractor must submit sample/s of materials and devices for approval by DBP before installation.

The Contractor shall designate or employ a full-time project coordinator that will supervise on-site works and activities.

DBP may terminate/cancel the Purchase Order (PO) / Notice to Proceed (NTP) when the Contractor fails to deliver, perform and comply with its obligation.

Project Period: The Contractor shall complete the project within thirty (30) calendar days after receipt of Purchase Order (PO) / Notice to Proceed (NTP).

Warranty: One (1) year warranty upon completion of all works.

Performance Security: To guarantee the faithful performance of obligations, the winning bidder is required to post within ten (10) calendar days from receipt of Notice of Award, a performance security (to expire upon completion of the project) in any of the following forms and percentages:

Forms of Performance Security Minimum % of Contract Price

Cash, cashier's/manager's check issued by a Universal or Commercial Bank. Ten Percent (10%)

Bank draft/guarantee or Irrevocable letter of credit issued by a Universal of Commercial Bank; provided, however, that it shall be confirmed or authenticated by a Universal of Commercial Bank, if issued by a foreign bank.

Surety Bond callable upon demand issued by a surety or insurance company duly certified by the Insurance Commission as authorized to issue such security. Thirty Percent (30%)

**PAYMENT:**

A one-time full payment shall be processed after the completion of the project subject to submission of the following complete documents:

Letter of Request for Payment  
Statement of Work Accomplishment'  
Contractor's Affidavit  
Project Pictures

**LIQUIDATED DAMAGES:**

Once the contract duration expires, including any time extension duly granted, and the Contractor refuses or fails to satisfactorily complete the work, DBP shall impose upon the Contractor in default liquidated damages. Liquidated damage is an amount equal to at least one tenth (1/10) of one (1) percent of the cost of the unperformed portion of the works for everyday of delay.

In case the total sum of liquidated damages reaches ten percent (10%) of the total contract price, DBP may terminate the contract or allow the contractor to continue the works without prejudice to the continued imposition of liquidated damages until the works have been completed. This does not, however, preclude DBP in resorting to Termination of Contract under Annex I of the 2016 revised IRR of RA No. 9184.

**DOCUMENTARY REQUIREMENTS**

Signed Quotation  
Valid and Current Business Permit  
Proof of PhilGEPS Registration  
Notarized Omnibus Sworn Statement signed by owner / authorized representative.  
For sole proprietorship, duly notarized special power of attorney, if to designate a representative.

**Created by** Jennifer Cordial Naval

**Date Created** 10/07/2025

The PhilGEPS team is not responsible for any typographical errors or misinformation presented in the system. PhilGEPS only displays information provided for by its clients, and any queries regarding the postings should be directed to the contact person/s of the concerned party.