



Bid Notice Abstract

Request for Quotation (RFQ)

Reference Number 12411715
Procuring Entity DBP BRANCH BANKING GROUP - BICOL
Title SUPPLY, DELIVERY, INSTALLATION AND TESTING & COMMISSIONING OF FIRE DETECTION ALARM SYSTEM FOR DBP LEGAZPI BRANCH, DBP DAET BRANCH, DBP IRIGA BRANCH AND DBP GUINOBATAN BRANCH
Area of Delivery Albay,Camarines Norte,Camarines Sur

Solicitation Number:	2025-021	Status	Pending
Trade Agreement:	Implementing Rules and Regulations		
Procurement Mode:	Negotiated Procurement - Small Value Procurement (Sec. 53.9)	Associated Components	10
Classification:	Goods	Bid Supplements	0
Category:	Fire Fighting & Rescue and Safety Equipment		
Approved Budget for the Contract:	PHP 839,757.92	Document Request List	0
Delivery Period:	60 Day/s		
Client Agency:		Date Published	19/09/2025
Contact Person:	Jennifer Cordial Naval Chairperson, RBAC-Bicol Panganiban Drive Naga City Camarines Sur Philippines 4400 63-2-88189511 Ext.1590 bbg@dbp.ph	Last Updated / Time	18/09/2025 11:23 AM
		Closing Date / Time	24/09/2025 15:00 PM

Description

LOCATION : DBP LEGAZPI BRANCH
DBP BUILDING QUEZON AVE., LEGAZPI CITY, ALBAY

DBP DAET BRANCH
MAGALLANES IRAYA, BRGY. III, DAET CAMARINES NORTE 4600

DBP IRIGA BRANCH
ICT BUILDING, POBLACION ROAD, STA. CRUZ SUR, IRIGA CITY

DBP GUINOBATAN BRANCH
GF SB LEGISLATIVE BUILDING, ILAWOD, GUINOBATAN CITY, ALBAY

SUBJECT : SCOPE OF WORKS AND TECHNICAL SPECIFICATIONS

MODE OF PROCUREMENT: SMALL VALUE PROCUREMENT (INFRASTRUCTURE)

APPROVED BUDGET FOR THE CONTRACT (ABC):
EIGHT HUNDRED THIRTY-NINE THOUSAND SEVEN HUNDRED FIFTY-SEVEN AND 92/100 (₱ 839,757.92) INCLUSIVE OF VAT/APPLICABLE TAXES

End User Approved Budget for Contract
DAET BRANCH ₱220,856.67
IRIGA BRANCH ₱208,878.40
GUINOBATAN BRANCH ₱184,247.53
LEGAZPI BRANCH ₱225,775.32
Total Contract Price ₱839,757.92

SCOPE OF WORKS AND TECHNICAL SPECIFICATIONS:

The Contractor shall hold all obligations, duties and responsibilities necessary for the successful completion of the contract assigned to or be undertaken, including all labor, materials, equipment and services, other incidentals, i.e., bonds and insurance, contractor's all risk insurance (CARI); and furnishings thereof in accordance with the specifications and all addenda prepared by DBP.

GENERAL REQUIREMENTS

Construction health and safety program
Clearances/permit requirements (certificate)
Mobilization & demobilization
Site maintenance
Hauling/disposal

SITE CONDITIONS

Dismantling Works
Dismantling of existing Fire Detection Alarm System (FDAS) device and Fire Alarm Panel, and properly turning over and securing the dismantled items in the DBP-designated storage area

FIRE DETECTION ALARM SYSTEM WORKS

IRIGA BRANCH

Installation of Fire Detection Alarm System and Accessories
New fire Alarm control panel (addressable) with batteries
New auto dialer (line / GSM Ready)
New smoke detector (addressable)
New heat detector (addressable)
New manual call point with strobe sounder (addressable)
Installation of wires and cables
CAT5e UTP cable 4 pairs (305m/box)
#16 2C AWG stranded TF wire
Installation of conduits and fittings
20mm dia PVC moulding (2.44m/pc)
PVC wire gutter with cover (2000mm Lx500mm Wx50mm D)
20mm dia flexible PVC pipe (50m/roll)
20mm dia straight connector
20mm dia angle connector
Installation of boxes
Junction box with cover (PVC)
Utility box (PVC)
Other accessories
Hanger and support
Consumables (tape, tagging, PVC cement and accessories)
Mounting termination, testing & commissioning and programming.

GUINOBATAN BRANCH

Installation of Fire Detection Alarm System and Accessories
Fire Alarm control panel (addressable)
auto dialer (line / GSM Ready)
Smoke detector (addressable)
Heat detector (addressable)
Manual call point with strobe sounder (addressable)
Installation of wires and cables
#16 2C AWG stranded TF wire
CAT5e UTP cable 4 pairs (305m/box)
Installation of conduits and fittings
25mm dia PVC pipe (3m/pc) with adapter and locknut
20mm dia flexible PVC pipe (50m/roll)
20mm dia straight connector
20mm dia angle connector
Installation of boxes
Junction box with cover (PVC)
Utility box (PVC)
Other accessories
Hanger and support
Consumables (tape, tagging, PVC cement and accessories)
Mounting termination, testing & commissioning and programming.

LEGAZPI BRANCH

3.3.1 Installation of Fire Detection Alarm System and Accessories

New fire Alarm control panel (addressable) with batteries

New auto dialer (line / GSM Ready)

New smoke detector (addressable)

New heat detector (addressable)

New manual call point with strobe sounder (addressable)

Installation of wires and cables

CAT5e UTP cable 4 pairs (305m/box)

#16 2C AWG stranded TF wire

3.3.3 Installation of conduits and fittings

25mm dia PVC pipe (3m/pc) with adapter and locknut

20mm dia flexible PVC pipe (50m/roll)

20mm dia straight connector

20mm dia angle connector

Installation of boxes

Junction box with cover (PVC)

Utility box (PVC)

Other accessories

Hanger and support

Consumables (tape, tagging, PVC cement and accessories)

Mounting termination, testing & commissioning and programming.

DAET BRANCH

Installation of Fire Detection Alarm System and Accessories

Fire Alarm control panel (addressable)

auto dialer (line / GSM Ready)

Smoke detector (addressable)

Heat detector (addressable)

Manual call point with strobe sounder (addressable)

Installation of wires and cables

#16 2C AWG stranded TF wire

CAT5e UTP cable 4 pairs (305m/box)

Installation of conduits and fittings

25mm dia PVC pipe (3m/pc) with adapter and locknut

20mm dia flexible PVC pipe (50m/roll)

20mm dia straight connector

20mm dia angle connector

Installation of boxes

Junction box with cover (PVC)

Utility box (PVC)

Other accessories

Hanger and support

Consumables (tape, tagging, PVC cement and accessories)

Mounting termination, testing & commissioning and programming.

CONDITIONS OF THE CONTRACT:

The Contractor shall ensure that the items delivered are in accordance with the specifications required by DBP. DBP has the right to reject delivery if item/s delivered were found to be defective and not according to the required specifications.

The Contractor shall submit, construction schedule reflecting all activities needed to complete the project, their sequence and duration.

The Contractor must submit sample/s of materials and devices for approval by DBP before installation.

The Contractor shall designate or employ a full-time project coordinator that will supervise on-site works and activities.

DBP may terminate/cancel the Purchase Order (PO) / Notice to Proceed (NTP) when the Contractor fails to deliver, perform and comply with its obligation.

Project Period: The Contractor shall complete the project within thirty (30) calendar days after receipt of Purchase Order (PO) / Notice to Proceed (NTP).

Warranty: One (1) year warranty upon completion of all works.

Performance Security: To guarantee the faithful performance of obligations, the winning bidder is required to post within ten (10) calendar days from receipt of Notice of Award, a performance security (to expire upon completion of the project) in any of the following forms and percentages:

Forms of Performance Security Minimum % of Contract Price

Cash, cashier's/manager's check issued by a Universal or Commercial Bank. Ten Percent (10%)

Bank draft/guarantee or Irrevocable letter of credit issued by a Universal of Commercial Bank; provided, however, that it shall be confirmed or authenticated by a Universal of Commercial Bank, if issued by a foreign bank.

Surety Bond callable upon demand issued by a surety or insurance company duly certified by the Insurance Commission as authorized to issue such security. Thirty Percent (30%)

PAYMENT:

A one-time full payment shall be processed after the completion of the project subject to submission of the following complete documents:

Letter of Request for Payment
Statement of Work Accomplishment'
Contractor's Affidavit
Project Pictures

LIQUIDATED DAMAGES:

Once the contract duration expires, including any time extension duly granted, and the Contractor refuses or fails to satisfactorily complete the work, DBP shall impose upon the Contractor in default liquidated damages. Liquidated damage is an amount equal to at least one tenth (1/10) of one (1) percent of the cost of the unperformed portion of the works for everyday of delay.

In case the total sum of liquidated damages reaches ten percent (10%) of the total contract price, DBP may terminate the contract or allow the contractor to continue the works without prejudice to the continued imposition of liquidated damages until the works have been completed. This does not, however, preclude DBP in resorting to Termination of Contract under Annex I of the 2016 revised IRR of RA No. 9184.

DOCUMENTARY REQUIREMENTS

Signed Quotation
Valid and Current Business Permit
Proof of PhilGEPS Registration
Notarized Omnibus Sworn Statement signed by owner / authorized representative.
For sole proprietorship, duly notarized special power of attorney, if to designate a representative.

-END-

Other Information

For clarifications, you may contact:

Jocel Amor C. Nobleza
Email Add: jatcaceres@dbp.ph, bbg@dbp.ph
Contact No.: (02) 8818-9511 local 1590

Created by Jennifer Cordial Naval

Date Created 18/09/2025

The PhilGEPS team is not responsible for any typographical errors or misinformation presented in the system. PhilGEPS only displays information provided for by its clients, and any queries regarding the postings should be directed to the contact person/s of the concerned party.