

PROJECT : Supply, Delivery and Installation of ATM Sunshade at DBP Basilan Branch
LOCATION : AC Infante, Inc. Building , JS Alano Street, Isabela City, Basilan
SUBJECT : Bill of Quantities

ITEM / SCOPE OF WORKS	Qty	Unit	Labor and Mat'ls	Mark up		Total Mark-up		VAT	Total Indirect Cost	Total Cost	Unit Cost
			Direct Cost	OCM	Profit	%	Value				
1.0 GENERAL REQUIREMENTS											
1.1 Mobilization/Demobilization (inclusive of freight cost)	1.00	lot		-	-						
1.2 Permit and Clearances	1.00	lot									
1.3 Construction and Health Safety											
1.3.1 Health and Safety Equipment (PPE)	1.00	lot		-	-						
1.4 General Cleaning and Hauling of Debris											
1.4.1 General Cleaning	1.00	lot		-	-						
1.4.2 Hauling of Debris	1.00	lot		-	-						
Sub-total											
2.0 STEEL WORKS											
2.1 Stainless Steel Framing											
2.1.1 45mm outside diameter stainless steel pipe (6m length)	1.00	pc		-	-						
2.1.2 6mm x 20mm stainless clip (for polycarbonate)	6.00	lm		-	-						
2.1.3 6mm Cover Plate	2.00	pcs		-	-						
2.1.4 Stainless Steel Countersunk Screw	8.00	pcs		-	-						
2.1.5 Consumables	1.00	lot		-	-						
Sub-total											
3.0 ATM SUNSHADE											
3.1 Polycarbonate											
3.1.1 6mm thk. Solid Clear Polycarbonate Sheet	1.00	sht.		-	-						
3.2 Decals											
3.2.1 DBP Logo & ATM Decals	1.00	set		-	-						
3.2.2 Vinyl Sticker, Pantone Color: Sultan Blue (reverse installation)	31.00	sq.ft		-	-						
Sub-total											
Total Cost											

PREPARED BY:

Name of Company: _____

By:

Printed Name and Signature