

NOTE 1: THE BID DRAWINGS & THE BOQ FORMS ARE PART OF THE CONTRACT. IT IS THE RESPONSIBILITY OF THE BIDDER TO INDICATE/INCLUDE IN THIS BOQ, WORK ITEMS SHOWN IN THE BID DRAWINGS THAT ARE NOT INDICATED IN THIS BOQ. IN CASES THIS WILL NOT BE REFLECTED IN THE BOQ, WORK ITEM INDICATED IN THE BID DRAWINGS SHALL BE IMPLEMENTED AT NO ADDITIONAL COST TO DBP. AS BID DRAWINGS FORM PART OF THE CONTRACT. ADDITIONAL COST WILL ONLY BE ENDORSED IF THIS IS NOT PART OF THE BID DRAWINGS.

NOTE 2: SUBMIT ALL SAMPLES FOR APPROVAL OF THE DBP. NO PURCHASE & INSTALLATION TO BE DONE WITHOUT DBP'S APPROVAL.

SUPPLY, DELIVERY AND INSTALLATION OF DBP SIGNAGE

Project Name

DBP BASILAN BRANCH, J.S. ALANO STREET, SEASIDE BARANGAY, ISABEL CITY, BASILAN

Project Location

ESTIMATED COST OF PROPOSED WORK

ITEM	DESCRIPTION	QTY	UNIT	ESTIMATED DIRECT COST (LABOR & MAT'LS)	MARK-UP		TOTAL MARK-UP		VAT	TOTAL INDIRECT COST	TOTAL COST	UNIT COST
					OCM	PROFIT	%	VALUE				
1	GENERAL REQUIREMENTS											
1.1	Mobilization/demobilization	1.00	lot	0.00	-	-	0%	0.00	0.00	0.00	0.00	0.00
1.2	Health and safety	1.00	lot	0.00	-	0.00	10%	0.00	0.00	0.00	0.00	0.00
1.3	Scaffolding	1.00	lot	0.00	0.00	0.00	25%	0.00	0.00	0.00	0.00	0.00
1.4	General cleaning/hauling of debris	1.00	lot	0.00	0.00	0.00	25%	0.00	0.00	0.00	0.00	0.00
sub-total											0.00	
2	METAL WORKS											
2.1	Steel post: 6.00m x 150mm dia. BI pipe	1.00	unit	0.00	0.00	0.00	25%	0.00	0.00	0.00	0.00	0.00
2.2	Other item of work necessary to complete the intent of the plan and specs (specify):											
	- Consumables (welding rod, tie wire, etc)	1.00	lot	0.00	-	0.00	10%	0.00	0.00	0.00	0.00	0.00
sub-total											0.00	
3	FINISHES											
3.1	Painting works											
	3.1.1 Steel post - primer and 2 coats of automotive paint (color: silver)	1.00	lot	0.00	0.00	0.00	25%	0.00	0.00	0.00	0.00	0.00
3.2	Other item of work necessary to complete the intent of the plan and specs (specify):											
	- Consumables (paint brush/roller, rags, sandpaper, paint thinner. etc)	1.00	lot	0.00	-	0.00	10%	0.00	0.00	0.00	0.00	0.00
sub-total											0.00	
4	SPECIALTIES											
4.1	Flag-type signage: double-faced panaflex, metal-framed with translucent sticker and LED lights											
	4.1.1 1.50m x 1.50m x 0.20m and 1.50m x 0.45m x 0.20m	1.00	set	0.00	0.00	0.00	25%	0.00	0.00	0.00	0.00	0.00
sub-total											0.00	
5	ELECTRICAL											
5.1	Timer switch	1.00	set	0.00	0.00	0.00	25%	0.00	0.00	0.00	0.00	0.00
5.2	Magnetic Contactor	1.00	set	0.00	0.00	0.00	25%	0.00	0.00	0.00	0.00	0.00
5.3	Breaker (20 amps; 2 pole MCB)	1.00	set	0.00	0.00	0.00	25%	0.00	0.00	0.00	0.00	0.00
5.4	3.5mm sq. THHN	1.00	box	0.00	0.00	0.00	25%	0.00	0.00	0.00	0.00	0.00
5.5	NEMA1 enclosure	1.00	set	0.00	0.00	0.00	25%	0.00	0.00	0.00	0.00	0.00
5.6	Other item of work necessary to complete the intent of the plan and specs (specify):											
	- Tapping to available power supply including (conduit pipes and fittings)	1.00	lot	0.00	0.00	0.00	25%	0.00	0.00	0.00	0.00	0.00
	- Consumables	1.00	lot	0.00	-	0.00	10%	0.00	0.00	0.00	0.00	0.00
sub-total											0.00	
TOTAL COST											0.00	

Prepared by: _____

Designation: _____

Date: _____