

Development Bank of the Philippines

PROJECT : SUPPLY, DELIVERY, INSTALLATION, TESTING AND

COMMISSIONING OF CCTV SURVEILANCE SYSTEM FOR DBP DAET

BRANCH

LOCATION : J. P. RIZAL STREET, DAET, BICOL

SUBJECT: SCOPE OF WORKS AND TECHNICAL SPECIFICATION

MODE OF PROCUREMENT: SMALL VALUE PROCUREMENT (INFRASTRUCTURE)

I. APPROVED BUDGET FOR THE CONTRACT: ONE HUNDRED FORTY-THREE THOUSAND TWO HUNDRED FIFTY-TWO AND 39/100 PESOS — ₱ 143, 252.39 (INCLUSIVE OF VAT/APPLICABLE TAXES)

II. SCOPE OF WORKS AND TECHNICAL SPECIFICATIONS:

The Contractor shall hold all obligations, duties and responsibilities necessary for the successful completion of the contract assigned to or be undertaken, including all labor, materials, equipment and services, other incidentals, i.e., bonds and insurance, contractor's all risk insurance (CARI); and furnishings thereof in accordance with the specifications and all addenda prepared by DBP.

1. GENERAL REQUIREMEN

- 1.1 Construction health and safety program
- 1.2 Mobilization and demobilization
- 1.3 Site Maintenance
 - 1.3.1 Hauling/ disposal

2. SITE CONDITIONS

- 2.1. Dismantling works
 - Dismantling of the existing CCTV Surveillance System devices and Panel, and properly turning over and securing the dismantled items in the DBPdesignated storage area

3. ELECTRONIC SECURITY SYSTEM

- 3.1. Installation of CCTV Surveillance System and Accessories
 - 3.1.1. 9U CCTV Cabinet (wall mounted)
 - 3.1.2. 5MP CCTV Camera (bullet type)
 - 3.1.3. 5MP CCTV Camera (dome type)
- 3.2. Installation of wires and cables
 - 3.2.1. Cat5e UTP cable 4 pairs (305m/box)
- 3.3. Installation of conduits and fittings
 - 3.3.1. 25.4mm dia EMT conduit (3m/pc)
 - 3.3.2. 25.4mm dia EMT elbow
 - 3.3.3. 25.4mm dia EMT coupling and connector (compression type)
 - 3.3.4. 25mmØ PVC pipe (3m/pc) with adapter and locknut
 - 3.3.5. 20mmØ flexible PVC pipe (50m/roll)
 - 3.3.6. 20mmØ straight connector
 - 3.3.7. 20mmØ angle connector
- 3.4. Installation of boxes
 - 3.4.1. Pullbox (ga#16)
 - 3.4.2. Junction box with cover (PVC)
- 3.5. C accessories
 - 3 Hanger and support
 - 3 Consumables (tape, tagging, PVC cement and accessories)

3.5.3. Mounting termination, testing & commissioning and programming.

Notes:

- Contractor must provide same brand with the existing CCTV system.
- In case of discrepancies between the working drawings and Technical Specifications, the Contractor shall coordinate, verify and confirm with DBP before proceeding with the works.
- Contractor must conduct an inspection and verify actual measurements on project site.
- Contractor shall ensure to isolate the power supply of the renovation affected area before starting the work.
- All work items cited above are based on the approved plans.
- Contractor must remove left over materials and debris from work area.
- Always refer to the Technical Specifications for details.

For clarifications or further details on Scope of Works/Technical Specifications, the contractor shall coordinate, verify and confirm first with DBP before proceeding with the works by submitting a Request for Information (RFI) memo addressed to the Head of Construction and Facilities Management Department (CFMD)

III. CONDITIONS OF THE CONTRACT:

- 1. The Contractor shall ensure that the items delivered are in accordance with the specifications required by the DBP. DBP has the right to reject delivery if item/s delivered were found to be defective and not according to the required specifications/model.
- 2. The Contractor shall submit, construction schedule reflecting all activities needed to complete the project, their sequence and duration.
- 3. The Contractor must submit sample/s of materials and devices for approval by DBP before installation.
- 4. The Contractor shall designate or employ a full-time project coordinator that will supervise on-site works and activities.
- 5. The DBP may terminate/cancel the Purchase Order (PO)/Notice to Proceed (NTP) when the contractor fails to deliver, perform and comply with its obligation.
- 6. **Project Period:** The Contractor shall complete the supply, delivery, installation, testing and commissioning of the CCTV Surveillance System for DBP Daet Branch within **Thirty (30) calendar days** after receipt of Purchase Order (PO) / Notice to Proceed (NTP).
- 7. Warranty: One (1) year warranty upon acceptance of items by DBP.

8. **Performance Security**: To guarantee the faithful performance of obligations, the winning bidder is required to post within ten (10) calendar days from receipt of Notice of Award, a performance security (to expire upon completion of the project) in any of the following forms and percentages:

Forms of Performance Security	Minimum % of Contract Price
Cash, cashier's/manager's check issued by a Universal or Commercial Bank.	
Bank draft/guarantee or Irrevocable letter of credit issued by a Universal of Commercial Bank; provided, however, that it shall be confirmed or authenticated by a Universal of Commercial Bank, if issued by a foreign bank.	Ten Percent (10%)
Surety Bond callable upon demand is issued by a surety or insurance company duly certified by the Insurance Commission as authorized to issue such security.	Thirty Percent (30%)

IV. DOCUMENTARY REQUIREMENTS:

- Proposal/Quotation
- Proof PhilGEPS Registration
- 2025 Mayor's/Business Permit
- Omnibus Sworn Statement
- Secretary Certificate (for Supplier under Partnership/Corporation)
- Signed Request for Quotation (RFQ)

V. PAYMENT:

A one-time full payment shall be processed after the completion of the project subject to submission of the following complete documents:

- Letter of Request for Payment
- Statement of Work Accomplishment'
- Contractor's Affidavit
- Project Pictures

VI. LIQUIDATED DAMAGES:

Once the contractor fails to satisfactorily complete the works under the contract within the specified contract duration, inclusive of duly granted time extensions, if any, the contractor shall be liable for liquidated damages in an amount equal to at least one-tenth (1/10) of one percent (1%) of the cost of the unperformed portion of the works for every day of delay.

In computing liquidated damages, the DBP shall determine the usability of the project. A project or a portion thereof may be deemed usable when it starts to provide the desired benefits as certified by the targeted End-User or Implementing Units and the DBP.

To be entitled to liquidated damages, the DBP does not have to prove that it has incurred actual damages. Such amount shall be deducted from any money due, or which may become due the contractor under the contract, collected from the retention money or other

securities posted by the contractor, or a combination thereof, whichever is convenient to the DBP.

In case the total sum of liquidated damages reaches ten percent (10%) of the total contract price, the DBP may rescind or terminate the contract, without prejudice to other courses of action and remedies available under the circumstances. This does not, however, preclude the DBP in resorting to Termination of Contract under Section 71.4 of the IRR of R.A. 12009.

-end-

Recommended by:

ENGR. JESSIE E. DELGADO

Acting Team Head, Luzon Team- PCMU

(Per Office Order No. 424 Dated 17 September 2025)

Approved by:

SM. ERICK M. VALIDO

Concurrent OIC, Construction & Facilities Management Department (Per Group Order No.4042 Dated 19 November 2025)

SUPPLY, DELIVERY, INSTALLATION TESTING AND COMMISSIONING OF CCTV SURVEILLANCE SYSTEM FOR DBP DAET BRANCH Project Name J. P. RIZAL STREET, DAET, BICOL Project Location

		143,252.39	Total=	THE REPORT OF THE PERSON NAMED IN								
DESCRIPTION QTY UNIT DIRECT COST O.G.M PROPRI TOTAL MARK-UP VATUE VA		121,989.893	Sub-total=					STATE STATE OF			SHEET STREET	
DESCRIPTION QTY. UNIT LABOR & MARTLS MARKAUP PROPRI TOTAL MARKAUP VATURE VATURE VATURE VATURE VATURE COST C	2,165.63	2,165.63	515.63	103.13	412.50	25%	165.00	247.50	1,650.00	lot	1	3.5.3 Mounting termination, testing, commissioning and programming
DESCRIPTION QTY. UNIT DABOR & MARYLLS MARKALP PROFIT 36 VALUE	1,270.5	1,270.50	170.50	60.50	110.00	10%	110.00		1,100.00	lot	_	3.5.2 Consumables (tape, tagging, PVC cement and accessories)
DESCRIPTION CITY LABOR & MARK-LUP PROFIT TOTAL MARK-LUP VAT TOTAL TOTAL VAT DESCRIPTION COST COST	1,443.7	1,443.75	343.75	68.75	275.00	25%	110.00	165.00	1,100.00	lot	1	3.5.1 Hanger and support
DESCRIPTION QTY. UNIT LABOR & MARK-LIP DIRECT COST OCM PROPIT TOTAL MARK-LIP AVAI MINDRECT COST OCM PROPIT TOTAL MARK-LIP OCM PROPIT OCM PROPIT TOTAL MARK-LIP OCM PROPIT TOTAL MARK												3.5 Other accessories
DESCRIPTION OTY. UNIT DIRECT COST OCM PROFIT TOTAL MARK-UP PROFIT TOTAL MARK-U	28.8	577.50	137.50	27.50	110.00	25%	44.00	66.00	440.00	set/s	20	3.4.2 Junction box with cover (PVC)
DESCRIPTION OTY. UNIT DIRECT COST OCM PROFIT % VALUE VALUE TOTAL MARK-UP COST OCM WINDRECT COST OCM WINDRECT COST OCM WINDRECT COST OCM OCM WINDRECT COST OCM	1,501.5	1,501.50	357.50	71.50	286.00	25%	114.40	171.60	1,144.00	set/s	1	3.4.1 Pullbox (ga#16)
DESCRIPTION OTT UNIT DIRECT COST OCM PROPIT TOTAL MARKUIP WAT WALUE VAT WALUE VAT COST										Section 199		3.4 Boxes
	27.5	551.25	131.25	26.25	105.00	25%	42.00	63.00	420.00	set/s	20	3.3.7 20mmØ angle connector
PRITION DITX UNIT LABOR & MATTLE MARK-LUP DIRECT COST OCM PROFIT 70 AL UE WAT MDIRECT COST	27.5	551.25	131.25	26.25	105.00	25%	42.00	63.00	420.00	set/s	20	3.3.6 20mmØ straight connector
DESCRIPTION OIT LABOR & MAT'LS MARK-UIP PROFIT % VALUE VAT MIDIRECT COST	490.8	981.75	233.75	46.75	187.00	25%	74.80	112.20	748.00	roll/s	2	3.3.5 20mmØ flexible PVC pipe (50m/roll)
DESCRIPTION DITY UNIT LABOR & MARTK-UP DIRECT COST OCM PROFIT % VALUE VAT TOTAL MARK-UP COST C	224.4	13,468.46	3,206.78	641.36	2,565.42	25%	1,026.17	1,539.25	10,261.68	set/s	60	3.3.4 25mmØ PVC pipe (3m/pc), with adapter and locknut
DESCRIPTION QTY. UNIT LABOR & MATK-UP DIRECT COST OCM DIRECT COST OCM PROFIT % VALUE VAT NUDIRECT COST	116.8	4,672.50	1,112.50	222.50	890.00	25%	356.00	534.00	3,560.00	set/s	40	3.3.3 25.4mm dia EMT coupling and connector (compression type)
CRIPTION QTY. UNIT LABOR & MAT'LS DIRECT COST OCM D	275.6	11,025.00	2,625.00	525.00	2,100.00	25%	840.00	1,260.00	8,400.00	pc/s	40	3.3.2 25.4mm dia EMT elbow
CRIPTION OTY. UNIT LABOR & MATI'S MARK-UP DIRECT COST OCM PROFIT % VALUE VAT NDIRECT COST COST	879.2	26,377.31	6,280.31	1,256.06	5,024.25	25%	2,009.70	3,014.55	20,097.00	pc/s	30	3.3.1 25.4mm dia EMT conduit (3m/pc)
												3.3 Conduits and fittings
CRIPTION OTY. UNIT LABOR & MATK-UP DIRECT COST OCM PROFIT WALUE VALUE COST CO	7,074.3	7,074.38	1,684.38	336.88	1,347.50	25%	539.00	808.50	5,390.00	box/es	_	3.2.1 Cat5e UTP cable 4 pairs (305m/box)
CATIFION CATIFIC CONT												3.2 Wires and cables
CRIPTION QTY. UNIT LABOR & MARK-LIP DIRECT COST OCM PROFIT % VALUE VAT NDIRECT COST C	7,536.3	22,609.13	5,383.13	1,076.63	4,306.50	25%	1,722.60	2,583.90	17,226.00	set/s	ω	3.1.3 5MP CCTV camera (dome type)
CRIPTION QTY. UNIT LABOR & MARK-UP DIRECT COST OCM PROFIT % VALUE VAT MDIRECT COST CO	7,536.3	15,072.75	3,588.75	717.75	2,871.00	25%	1,148.40	1,722.60	11,484.00	set/s	2	3.1.2 SMP CCTV camera (bullet type)
Construction health and safety program OTT	12,647.2	12,647.25	3,011.25	602.25	2,409.00	25%	963.60	1,445.40	9,636.00	set/s	1	3.1.1 9U CCTV Cabinet (wall mounted)
DESCRIPTION DITAL DIRECT COST DIREC												3.1 CCTV Surveillance System
DESCRIPTION DIRECT COST OCM DIRECT COST OCM PROFIT TOTAL MARK-UP VAT INDIRECT COST COS												3 ELECTRONIC SAFETY AND SECURITY
DESCRIPTION DITAL DIRECT COST OCM DI		6.562.500	Sub-total=	STATE OF STREET, STATE OF STREET, STATE OF STREET, STATE OF STATE OF STREET, STATE OF STREET, STATE OF STREET,		Water of Street	STATISTICS AND ADDRESS.					
GENERAL REQUIREMENTS 4 UNIT LABOR & MAT'LS DIRECT COST DIRECT COST DIRECT COST DOCM HOFIT PROFIT PR	6,562.5	6,562.50	1,562.50	312.50	1,250.00	25%	500.00	750.00	5,000.00	lot	1	2.1 Dismantling works
DESCRIPTION DITAL DIRECT COST DIREC												2 SITE CONDITIONS
DESCRIPTION QTY. UNIT LABOR & MARTILS MARK-UP MARK-UP		14,700.000	Sub-total=									
DESCRIPTION QTY. UNIT LABOR & MARTILS MARK-UP PROFIT MARK-UP PROFIT MARK-UP VAT INDIRECT COST COS	1,312.5	1,312.50	312.50	62.50	250.00	25%	100.00	150.00	1,000.00	lot		1.3.1 Hauling/disposal
DESCRIPTION QTY. UNIT LABOR & MARTILS MARK-UP PROFIT MARK-UP PROFIT MARK-UP VAT INDIRECT COST COS												1.3 Site maintenance
DESCRIPTION QTY. UNIT LABOR & MAT'LS MARK-UP PROFIT MARK-UP VAT TOTAL UNDIRECT COST C	10,500.0	10,500.00	500.00	500.00		0%	1		10,000.00	ot	_	1.2 Mobilization and demobilization
DESCRIPTION QTY. UNIT LABOR & MAT'LS MARK-UP PROFIT TOTAL MARK-UP VAT INDIRECT COST COST	2,887.5	2,887.50	387.50	137.50	250.00	10%	250.00		2,500.00	lot	_	1.1 Construction health and safety program
DESCRIPTION QTY. UNIT LABOR & MAT'LS MARK-UP PROFIT TOTAL MARK-UP VAT INDIRECT COST COST												1 GENERAL RECHIREMENTS
DITE OF MORNING	COST	COST	INDIRECT COST	_	VALUE	% A	PROFIT	OCM	DIRECT COST		QTY.	
		TOTAL STATE	10101		MADK HD	N. C.		MADKID	ABOD & MATH &	No. of the last of		

Prepared by:

ENGK. NAIGO IOWIE B. MOLINA JO- Technical Staff

Reviewed & Recommended by:

Approved by:

ENGR. JESSIR'E. PELGADO
Acting Head, PM HO, Luzon Team, PCMU-CFMD
(Per O.O. No. 424-dated 17 September 2025)

SM ERICK M. VALIDO
Concurrent OIC, Construction & Facilities Management Dept.
(Per Group Order No. 4042 dated 19 November 2025)

